



Particle Tracking Comparison

DCC Operation vs 3-Mile Sl. Operation

Particle Tracking Animation



Particle Tracking Animation



Franks Tract Pilot Project Construction Cost - Summary




Assumes use of Obermeyer operational gates.


Obermeyer Gates



Obermeyer Gate - Cross Section



Elevation of Gated Structure – Looking D/S




Franks Tract Pilot Project Budget

(2006 dollars)

Alternatives Eval. & Value Eng.	\$ 1 M
EIR/EIS and Permits	\$ 2 M
Monitoring Program (5 years)	\$ 5 M
Final Design	\$ 3 M
Construction	\$ 24 M
Construction Management	\$ 3 M
Total	\$ 38 Million

Assumes use of Obermeyer operational gates.

Franks Tract Pilot Project Schedule




Franks Tract Pilot Project

Funding Sources and Strategy

- Funding Strategy
 - 1/2 from State funds
(Water quality, Prop 84 and fish facility improvement, Prop 13)
 - 1/2 from water users (SWP, CVP, CCWD, et al)
 - Federal funding dependent on its study and legislation

Delta Cross Channel /Through Delta Facility



- DCC - an existing 3500 cfs diversion from the Sacramento River
- 4,000 cfs Sacramento River diversion near Hood. Returns to South Fork Mokelumne at New Hope Tract

Delta Cross Channel /Through Delta Facility


What we've learned to date

- Two dimensional modeling studies show:
 - Accurately simulate actual water quality data
 - Show potential for significant reduction in salinity for DCC/TDF/FT
 - Salinity reduction can be significantly improved with an operational structure

Delta Cross Channel

Field studies show:

- DDC operations have regional affects
- Circulation patterns at bends in rivers affect fish behavior
- Fish move in the water column - day and night conditions
- Reconfiguration of slough entrances may reduce fish entrainment



Delta Cross Channel/ Through Delta Facility

Summary of Salinity (EC) Reduction

	SWP	CVP	CCWD Old River	CCWD Rock Slough
TDF				
Sep 2002 (Dry)	26.2%	22.0%	27.1%	25.0%
TDF/FT				
Sep 2002 (Dry)	32.4%	26.5%	35.9%	35.1%
DCC Tidal				
Dec 1999 (Wet)*	6.9%	4.0%	10.4%	8.5%
DCC Dawn-Dusk				
Dec 1999 (Wet)*	12.5%	7.2%	19.3%	16.4%

* DCC closed thru Dec 14

TDF Major Features

- Intake Facility
 - Trash Rack
 - Floodgate
 - Fish Screens
 - Fish Bypass Channel
- Unlined canal
- Siphons at water crossings
- Bridges at major road crossing
- Pumping plant

Delta Cross Channel/ Through Delta Facility –Future Work Plan

- Continue water quality modeling for long-term operations
- Conduct a regional hydrodynamic/fish study
- Evaluate fishery impacts/benefits
- Develop project recommendations

Delta Cross Channel/Through Delta Facility Project Schedule

